

Temuka Water Event

DECEMBER 2017 – MARCH 2018

Ashley Harper, CPEng; FIPENZ
Infrastructure Group Manager
Timaru District Council





OUTLINE

1. Issue Definition
2. Location
3. Timeline
4. Water Safety
5. Design
6. Approvals
7. Contract Model
8. Installation
9. Critical Path
10. Risk Management
11. Commissioning
12. Communication
13. Learnings




1. Issue Definition

In early December 2017 the Temuka Water Supply was found to contain millions of Asbestos Fibres from an unknown source.

Within 114 days the problem was solved by installing a 9km replacement trunk water main.

2. Location



2. Location



3. Timeline

28 November	Calls from the Public – 'Lower Water Pressure'
5 December	'You have Asbestos'
12 December	Decision to install filter
17-20 December	Install/Commission Filter Plant
4 January	Trunk main burst
8 January	Design Workshop
9 January	Contractors Briefing
12 January	Extraordinary Council Meeting -Project to Replace Pipeline Approved • \$3.3m estimated cost • Completion prior to 31 March (Easter)

3. Timeline (cont'd)

12-19 January	Pipe Supply Tendering Programme
15-20 January	Pipe Install Tendering Programme
22/23 January	Tenders Let
29 January	Pipes start arriving
29 January	Welding commenced
4 February	Two further pipe bursts
7 February	New Pipe Installation commenced
19 March	80% (7.2km) installed and put into use
29 March	100% (9.0km) installed and in use
30 April	Project substantially completed
31 July	Completion

4. Water Safety

- Medical authorities stated and reconfirmed that Asbestos fibres in potable water did NOT compromise water safety
- Static tank of Timaru Water installed at the Temuka Service Centre carpark for resident self service
- Filtration Plant installation gave residents a degree of comfort

Filtration Units



Filtration Plant



AC Pipe





5. Design

- Current Trunk Main
 - 3km 2015 300mm PVC
 - 9km 1964 300mm AC 'Fibrolite' brand
- Options
 - 9km 1 x 300mm PVC
 - 9km 2 x 300mm PVC
 - 9km 1 x 450mm HDPE
- Features
 - 'In Line' valves @ 1.5km
 - Air valves
 - Sluice valves
 - Metering
 - PRV
 - PSV

450mm HDPE Pipes 29.01.2018



6. Approvals

- Land Entry - Farmers x3
 - KiwiRail
 - NZTA
- Consents - Canterbury Regional Council –unforeseen event
 - TDC 'exempt building' work

7. Contract Model

Timaru District Council

- Project Managers , Coordinators, Supervisors
- Supply all pipeline components
- Land entry agreements
- As built drawings
- Testing and commissioning

Contractors

- Weld Pipes
- Install Pipeline
- Install Fittings
- Connect to existing

Suppliers = 6

Contractors = 8

8. Installation

- 4 Zones/4 Contractors
- 4 Connections
- 1.5m max depth
- Avoid
 - Fibre Optics x3
 - Existing 300mm AC
 - Trunk Sewer – 300mm HDPE
 - State Highway 1

Zone 1



Zone 1: Pipe Install



Zone 1: Pipe Install



Zone 2



Zone 2: Pipe Install



Zone 3



Zone 3: Pipe Install



Zone 3: Backfilling



Zone 4: Bridge for Pipe



Zone 4: Pipe Install



Zone 4: Trench Testing



Zone 4:




Zone 4:



Zone 4:



Crossing Existing 300mm AC



Zone 4: Ground Water



19/02/2018 09:53

State H-Way 1 / Railway Crossing: Sheet Piling







9. Critical Path


10. Risk Management



11. Commissioning

- Testing
- Swabbing
- Sterilisation – Chlorination
- De-chlorination
- Cut Over





Zone 1: Pipe Filling



Zone 2: Winchester Connection



PRV Testing

20.03.2018



All Zones: Chlorination





12. Communications

- All Media - 5 December 2017 Evening
- TV Interviews - 7 December 2017
- Leaflet Drop to every household mid January 2018
- Internal updates every week
- Facebook actively managed
- Minimal newspaper interest
- Community Fun Day – 10 March 2018
- Completion Notification – 29 March 2018

13. Learnings

- Was the AC Pipe Sampling Programme sufficiently robust?
- What is the real life expectancy of AC Pipe?